


FILLED CELL DIMENSIONS
ARE LOCATED FROM
PLANS PROVIDED. DOOR &
WINDOW OPENINGS SHALL
BE COORDINATED WITH
SPECIFIC MANUFACTURER.



FOUNDATION LEGEND

SYMBOL	DESIGN DESCRIPTION
■	INDICATES FILLED CELL w/3000 PSI CONCRETE CONSTRUCTED PER DETAIL MS01/SN AND SPACED PER PLAN
□	INDICATES FILLED CELL BELOW WINDOWS w/3000 PSI CONCRETE CONSTRUCTED PER DETAIL MS01/SN AND SPACED PER PLAN
F#.#	INDICATES CONCRETE FOOTING w/ MINIMUM SOIL BEARING CAPACITY OF 2000 PSF. REINFORCE PER GENERAL FOUNDATIONS SCHEDULE ON SHEET SN FOR DESIGN SPECIFICATIONS.
	INDICATES CONSTRUCTION JOINT (IF SHOWN) SHALL BE 1/2" x 1" SAW CUTS FILLED WITH APPROVED SLAB JOINT MATERIAL COVERING A 12"x12" SQUARE MAXIMUM
≡	INDICATES STEP IN FOUNDATION, VERIFY PER ARCHITECTURAL PLANS CONSTRUCT PER PLAN SECTION CUT AND DETAIL SHEET D1
0'-0" FIN. FLR.	4" 2500 PSI CONC. SLAB W/ REINF. PER S0 w/6 MIL VISQUEEN VAPOR BARRIER & TREATED FOR TERMITES. SEE FOUNDATION SCHEDULE ON SN
	INDICATES BUILT UP COLUMN, SEE FRAMING PLAN FOR SIZE, DETAIL WF37/SN FOR PLY ATTACHMENT, AND UPLIFT CONNECTION SCHEDULE ON SN FOR CONNECTION TO SLAB

GENERAL NOTES:

- TYPICAL CORNER FRAMING PER DETAIL FM19/D1
- SEE ARCHITECTURAL PLANS FOR ALL SLAB STEP DEPTHS IF SHOW SHOWN WITHIN THESE DOCUMENTS.

FILLED CELL NOTES:

- SEE PLAN FOR ZONE MIDDLE AND END DESIGNATIONS
- PLACE FILLED CELLS AT ALL BUILDING CORNER, UNDER GIRDERS, BOTH ENDS OF EXTERIOR WALL OPENING, AND WHERE INTERIOR BEARING WALLS ARE PERPENDICULAR TO EXTERIOR MASONRY WALL.
- PLACE 1-#5 IN FIRST TWO CELLS ADJACENT TO GARAGE DOOR OPENING & ALL OPENINGS 8'-0" & LARGER. FILL CELLS SOLID.
- PLACE 1-#5 WHERE WOOD BEAMS CONNECT TO MASONRY WALL
- NO NOT PLACE FILLED CELLS DIRECTLY IN LINE w/ STOVE VENT

PLAN KEY NOTES

- 12" x 12" CMU COL. w/ (2) #5 - T/COL. EL. 9'-4" A.F.F.

BUILDER NOTE:
ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN PROFESSIONAL FOR CLARIFICATION PRIOR TO COMMENCEMENT OF CONSTRUCTION

WALL TYPE	
SYMBOL	DESIGN DESCRIPTION
	2x INTERIOR BEARING SHEARWALL - SEE BEARING WALL SCHEDULE ON SHEET SN FOR REQUIREMENTS.
	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN
	MASONRY WALL TOP @ 9'-4"
	MASONRY WALL TOP @ 10'-8" ABV. GRADE
	MASONRY WALL TOP @ 10'-8" ABV. GRADE

KEY PLAN

FOUNDATION PLAN

SCALE: 1/4" = 1'-0"

B&A Design Studio, Inc.

4017 W. 1st Street
Sanford, FL 32771
ph 407 829 8900
fax 407 829 2040
www.badesignstudios.com

www.FDSBENG.COM

FDS ENGINEERING ASSOCIATES
288 Southhall Lane, Suite 200, Maitland, FL 32751
Professional Engineer
Certificate of Authorization No. 9191
□ CARLA A. BROWN, PE - FL #45628
□ SCOTT LEWIS, PE - FL #27890
DATE: November 9, 2023
THIS DRAWING IS THE PROPERTY OF B&A DESIGN STUDIO, INC. AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT PERMISSION IN WRITING FROM B&A DESIGN STUDIO, INC.

PARK SQUARE
HORIZONS WEST
4-UNIT - ADAMS END UNITS


title:

project no. 2022142
checked: AB
drawn: AB
date: 05-17-22
scale:

S1.1

NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED

FILLED CELL DIMENSIONS
ARE LOCATED FROM
PLANS PROVIDED. DOOR &
WINDOW OPENINGS SHALL
BE COORDINATED WITH
SPECIFIC MANUFACTURER.



FOUNDATION LEGEND

SYMBOL	DESIGN DESCRIPTION
■	INDICATES FILLED CELL w/3000 PSI CONCRETE CONSTRUCTED PER DETAIL MS01/SN AND SPACED PER PLAN
□	INDICATES FILLED CELL BELOW WINDOWS w/3000 PSI CONCRETE CONSTRUCTED PER DETAIL MS01/SN AND SPACED PER PLAN
F# #	INDICATES CONCRETE FOOTING w/ MINIMUM SOIL BEARING CAPACITY OF 2000 PSF. REINFORCE PER GENERAL FOUNDATIONS SCHEDULE ON SHEET SN FOR DESIGN SPECIFICATIONS.
	INDICATES CONSTRUCTION JOINT (IF SHOWN) SHALL BE 1/2" x 1" SAW CUTS FILLED WITH APPROVED SLAB JOINT MATERIAL COVERING A 12"x12" SQUARE MAXIMUM
4"	INDICATES STEP IN FOUNDATION, VERIFY PER ARCHITECTURAL PLANS CONSTRUCT PER PLAN SECTION CUT AND DETAIL SHEET D1
0'-0" FIN. FLR.	4" 2500 PSI CONC. SLAB W/ REINF. PER S0 w/6 MIL VISQUEEN VAPOR BARRIER & TREATED FOR TERMITES. SEE FOUNDATION SCHEDULE ON SN
	INDICATES BUILT UP COLUMN, SEE FRAMING PLAN FOR SIZE, DETAIL WF37/SN FOR PLY ATTACHMENT, AND UPLIFT CONNECTION SCHEDULE ON SN FOR CONNECTION TO SLAB

GENERAL NOTES:
1. TYPICAL CORNER FRAMING PER DETAIL FM19/D1
2. SEE ARCHITECTURAL PLANS FOR ALL SLAB STEP DEPTHS IF SHOWN WITHIN THESE DOCUMENTS.

FILLED CELL NOTES:
1. SEE PLAN FOR ZONE MIDDLE AND END DESIGNATIONS
2. PLACE FILLED CELLS AT ALL BUILDING CORNER, UNDER GIRDERS, BOTH ENDS OF EXTERIOR WALL OPENING, AND WHERE INTERIOR BEARING WALLS ARE PERPENDICULAR TO EXTERIOR MASONRY WALL.
3. PLACE 1-#5 IN FIRST TWO CELLS ADJACENT TO GARAGE DOOR OPENING & ALL OPENINGS 8'-0" & LARGER. FILL CELLS SOLID.
4. PLACE 1-#5 WHERE WOOD BEAMS CONNECT TO MASONRY WALL
5. NO NOT PLACE FILLED CELLS DIRECTLY IN LINE w/ STOVE VENT

PLAN KEY NOTES

BUILDER NOTE:
ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN PROFESSIONAL FOR CLARIFICATION PRIOR TO COMMENCEMENT OF CONSTRUCTION

WALL TYPE	
SYMBOL	DESIGN DESCRIPTION
	2x INTERIOR BEARING SHEARWALL - SEE BEARING WALL SCHEDULE ON SHEET SN FOR REQUIREMENTS.
	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN
	MASONRY WALL TOP @ 9'-4"
	MASONRY WALL TOP @ 10'-8" ABV. GRADE
	MASONRY WALL TOP @ 10'-8" ABV. GRADE

KEY PLAN

FOUNDATION PLAN

SCALE: 1/4" = 1'-0"

B&A Design Studio, Inc.

4017 W. 1st Street
Sanford, FL 32771
ph: 407 829 8900
fax: 407 829 2040
www.badesignstudios.com

N.C.B.D.C.

AMERICAN INSTITUTE OF DESIGN

www.FDSBENG.COM

FDS

ENGINEERING ASSOCIATES
288 Southhall Lane, Suite 200, Maitland, FL 32751
Phone: 407-829-8900
Fax: 407-829-2040
Email: info@fdesa.com
Certificate of Authorization No. 9191
CARL A. BROWN, PE, FL #5628
SCOTT LEWIS, PE, FL #78790
DATE: November 9, 2023

THIS SEAL IS THE PROPERTY OF THE ENGINEER AND MUST BE USED ONLY FOR THE PROJECT AND DATE INDICATED THEREON. IT IS TO BE USED ONLY FOR THE PROJECT AND DATE INDICATED THEREON.

**PARK SQUARE
HORIZONS WEST
4-UNIT - ADAMS END UNITS**

title:

project no. 2022142
checked:
drawn: AB
date: 05-17-22
scale:

S1.2

NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED

RSH

ENGINEERED ROOF PER ASCE 7-16 ROOF DESIGN ALLOWABLE COMPONENTS AND CLADDING WIND PRESSURES AND SUCTIONS FOR MEAN ROOF HEIGHT ≤ 25 ft

WIND SPEED (ULTIMATE)

WIND SPEED (ALLOWABLE)

EXPOSURE CATEGORY

140.0 MPH

108.4 MPH

C


EFFECTIVE WIND AREA (SQ FEET)


WIND PRESSURE AND SUCTION (PSF)







(+) VALUE DENOTES PRESSURE

(-) VALUE DENOTES SUCTION

AREA	ROOF	1	2e	2n	2r	3	3e	3r
10	HIP	-35.94	-49.57		-49.57	-49.57		
	GABLE	-38.22	-38.22	-60.99	-60.99		-60.99	-78.58

ROOF NAILING SCHEDULE/ NAILING ZONES (SHINGLE AND TILE):
ZONE 1: ASTM F1667 RSR-01 (8d) NAILS @ 6" O.C. ON EDGE AND 6" O.C. IN FIELD
ZONE 2e, 2n, 2r: ASTM F1667 RSR-01 (8d) NAILS @ 4" O.C. ON EDGE AND 4" O.C. IN FIELD
ZONE 3, 3e, 3r: ASTM F1667 RSR-01 (8d) NAILS @ 4" O.C. ON EDGE AND 4" O.C. IN FIELD
ROOF SHEATHING:
SHINGLE: 7/16" EXP. 1 (2^{1/2})₁₆ or 15/32" EXP. 1 (2^{1/2})₁₆
TILE: 15/32" EXP. 1 (2^{1/2})₁₆
NOTE:
1. PER CODE ASTM F1667 RSR-01 REFERENCE TO 8d (2 3/8" x 0.113") NAILS
2. WHERE THE SHEATHING THICKNESS IS GREATER THAN 15/32", SHEATHING SHALL BE FASTENED WITH ASTM F1667 RSR-03 10d (2 1/2" x 0.131") NAILS OR ASTM F1667 RSR-04 (3" x 12d) NAILS
3. GABLES- DROP GABLE END & (1) ADDITIONAL DROPPED TRUSS 2x4 #2 SYP OUTLOOKER RAFTER W/ BLOCKING @ 16" O.C. IF NO DROPPED GABLE END, ATTACH 2x4 #2 SYP BLOCKING @ 16" O.C. FIRST 4 BAYS WITH (2) 12d NAILS EA. END. ATTACH ROOF SHEATHING TO RAFTERS W/ BLOCKING PER NAILING SCHEDULE.
HIP ROOF >20 TO 27 DEG.
[4:12]-[6:12]

GABLE ROOF > 20 TO 27 DEG.
[4:12]-[6:12]



SYMBOL	DESIGN DESCRIPTION
	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN , SEE ARCHITECTURAL PLANS FOR WALL WIDTH, 2x4 MINIMUM U.O.N.
PSW	INDICATES PERFORATED SHEAR WALL, SEE ARCHITECTURAL PLANS FOR WALL WIDTH, 2x4 MINIMUM U.O.N.
	INDICATES BUILT UP COLUMN, SEE FRAMING PLAN FOR SIZE, DETAIL WF37/SN FOR PLY AT ARCHES AND UPLIFT CONNECTION SCHEDULE ON SN FOR CONNECTION TO SLAB
	INDICATES NO BOTTOM CONNECTOR REQUIRED
	INDICATES UPLIFT CONNECTION CONSTRUCTED PER DETAIL UPLIFT CONNECTOR SCHEDULE ON SHEET SN
	INDICATES WINDOW PRESSURE - SEE S0 FOR MORE INFORMATION.
	INDICATES LINTEL PER LINTEL PLAN

- FRAMING NOTES:
- SEE WIND SPEED CHART ON S0 FOR WINDOW PRESSURES
 - AT SECOND FLOOR FOR TYPICAL CORNER FRAMING SEE DETAIL FB06/D3

- GENERAL NOTES:
- THE FRAMING PLAN SHOWN INDICATES THE "TRUSS SYSTEM" AND IS THE RESPONSIBILITY OF THE TRUSS SYSTEM ENGINEER (DESIGN PROFESSIONAL OF RECORD). THE TRUSS DESIGN ENGINEER (DELEGATED ENGINEER) HAS FINAL, RESONSIBILITY FOR EACH INDIVIDUAL TRUSS AND TRUSS PROFILE, AND IS TO SUBMIT A FINAL SET OF TRUSS ENGINEERING SIGNED AND SEALED TRUSS DRAWINGS TO DESIGN PROFESSIONAL OF RECORD FOR REVIEW PRIOR TO FABRICATION
 - ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES WITH IN THIS PLAN SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN PROFESSIONAL FOR CLARIFICATION PRIOR TO CONSTRUCTION.
 - SEE SHEET SN FOR DESIGN SCHEDULES AND NOTES: FOUNDATION SCHEDULE / COLUMN SCHEDULE / BEARING WALL SCHEDULE / BEAM SCHEDULE / HEADER SCHEDULE / CONNECTION SCHEDULE / FLOOR AND ROOF NOTES.






PLAN KEY NOTES

- 12" SQ CMU COLUMN W/(2)#5 FULLY GROUTED
- LGUM28-3-SDS CONNECTOR BY SIMPSON STRONG TIE w/(6) 3/8"x4" TITEN HD ANCHORS TO MASONRY AND (6) 1/4"x2-1/2" STRONG DRIVE SDS SCREWS
- SIMPSON LGUM28-2-SDS w/ (6) 3/8"x4" TITEN HD ANCHORS TO MASONRY & (6) 1/4"x2-1/2" STRONG-DRIVE SDS SCREWS TO JOIST

BUILDER NOTE:
TRUSS LAYOUT, CONNECTORS & ENGINEERING BASED ON TRUSSES PROVIDED BY A-1 INDUSTRIES. PROJECT NAME CPSMU4 w/ TRUSS DESIGN DATED 4/24/23 IF THE TRUSS LAYOUT SHOWN DOES NOT MATCH THE TRUSS MANUFACTURERS LAYOUT AND DATE ABOVE

-----STOP-----

AND CALL THE ENGINEER OF RECORD PRIOR TO PLACEMENT OF ANY TRUSSES.

SYMBOL	DESIGN DESCRIPTION
	2x INTERIOR BEARING SHEARWALL - SEE BEARING WALL SCHEDULE ON SHEET SN FOR REQUIREMENTS.
	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN
	MASONRY WALL TOP @ 9'-4"
	MASONRY WALL TOP @ 10'-8" ABV. GRADE
	MASONRY WALL TOP @ 10'-8" ABV. GRADE

KEY PLAN

LOW ROOF & FLOOR FRAMING PLAN


SCALE: 1/4" = 1'-0"

B&A Design Studio, Inc.



4017 W. 1st Street
Seaford, FL 32771
ph: 407 829 8900
fax: 407 829 2040
www.badesignstudios.com

N.C.B.D.C.



AL
BD
AMERICAN
INSTITUTE OF
BUILDING DESIGNERS

FDS

ENGINEERING ASSOCIATES
288 Southhall Lane, Suite 200, Maitland, FL 32751
(407) 829-8900
Certificate of Authorization No. 9161

☐ CARL A. BROWN, PE, FL #45628
☐ SCOTT LEWISOWSKI, PE, FL #78790
DATE: November 9, 2023
THIS SEAL IS THE PROPERTY OF THE ENGINEER AND SHALL BE USED ONLY FOR THE PROJECT AND DATE INDICATED. IT IS TO BE RETURNED TO THE ENGINEER UPON COMPLETION OF THE PROJECT.


PARK SQUARE
HORIZONS WEST
4-UNIT - ADAMS END UNITS








title:

project no. 2022142
checked:
drawn: AB
date: 05-17-22
scale:

S2.1

NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED

[illegible]

SYMBOL	DESIGN DESCRIPTION
	INDICATES BEARING WALL. SEE BEARING WOOD BEARING SCHEDULE ON SN. SEE ARCHITECTURAL PLANS FOR WALL WIDTH, 2x4 MINIMUM U.O.N.
	INDICATES PERFORATED SHEAR WALL. SEE ARCHITECTURAL PLANS FOR WALL WIDTH, 2x4 MINIMUM U.O.N.
	INDICATES BUILT UP COLUMN. SEE FRAMING PLAN FOR SIZE. DETAIL WF37/SN FOR PLY ATTACHMENT AND UPLIFT CONNECTION SCHEDULE ON SN FOR CONNECTION TO SLAB
	INDICATES NO BOTTOM CONNECTOR REQUIRED
	INDICATES UPLIFT CONNECTION CONSTRUCTED PER DETAIL UPLIFT CONNECTOR SCHEDULE ON SHEET SN
	INDICATES WINDOW PRESSURE - SEE S0 FOR MORE INFORMATION.
	INDICATES LINTEL PER LINTEL PLAN

- FRAMING NOTES:**
1. SEE WIND SPEED CHART ON S04 FOR WINDOW PRESSURES
 2. AT SECOND FLOOR FOR TYPICAL CORNER FRAMING SEE DETAIL **F806/D3**
- GENERAL NOTES:**
1. THE FRAMING PLAN SHOWN INDICATES THE "TRUSS SYSTEM" AND IS THE RESPONSIBILITY OF THE TRUSS SYSTEM ENGINEER (DESIGN PROFESSIONAL OF RECORD), THE TRUSS DESIGN ENGINEER (DELEGATED ENGINEER) HAS FINAL RESPONSIBILITY FOR EACH INDIVIDUAL TRUSS AND TRUSS PROFILE, AND IS TO SUBMIT A FINAL SET OF TRUSS ENGINEERING SIGNED AND SEALED TRUSS DRAWINGS TO THE DESIGN PROFESSIONAL OF RECORD FOR REVIEW PRIOR TO FABRICATION
 2. ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES WITH IN THIS PLAN SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN PROFESSIONAL FOR CLARIFICATION PRIOR TO CONSTRUCTION.
 3. SEE SHEET SN FOR DESIGN SCHEDULES AND NOTES: BEARING WALL SCHEDULE / COLUMN SCHEDULE / BEARING WALL SCHEDULE / BEAM SCHEDULE / HEADER SCHEDULE / CONNECTION SCHEDULE / FLOOR AND ROOF NOTES.

PLAN KEY NOTES

- 1 12" SQ CMU COLUMN W/(2)#5 FULLY GROUTED
- 2 LGUM28-3-SDS CONNECTOR BY SIMPSON STRONG TIE w/(6) 3/8"x4" TITEN HD ANCHORS TO MASONRY AND (6) 1/4"x2-1/2" STRONG DRIVE SDS SCREWS
- 3 SIMPSON LGUM28-2-SDS w/ (6) 3/8"x4" TITEN HD ANCHORS TO MASONRY & (6) 1/4"x2-1/2" STRONG-DRIVE SDS SCREWS TO JOIST


BUILDER NOTE:

TRUSS LAYOUT, CONNECTORS & ENGINEERING BASED ON
TRUSSES PROVIDED BY A-1 INDUSTRIES, PROJECT NAME
CPSMU4 w/ TRUSS DESIGN DATED 4/24/23 IF THE TRUSS
LAYOUT SHOWN DOES NOT MATCH THE TRUSS
MANUFACTURERS LAYOUT AND DATE ABOVE

---STOP---

AND CALL THE ENGINEER OF RECORD PRIOR TO
PLACEMENT OF ANY TRUSSES.

WALL TYPE	
SYMBOL	DESIGN DESCRIPTION
	2x. INTERIOR BEARING SHEARWALL - SEE BEARING WALL SCHEDULE ON SHEET SN FOR REQUIREMENTS.
	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN
	MASONRY WALL TOP @ 9'-4"
	MASONRY WALL TOP @ 10'-8" ABV. GRADE
	MASONRY WALL TOP @ 10'-8" ABV. GRADE



KEY PLAN FRAMING PLAN

SCALE: 1/4" = 1'-0"



**B&A Design
Studio,
Inc.**

4017 W. 1st Street
Sanford, FL 32771
ph 407 829 8900
fax 407 829 2040
www.badesignstudios.com

N · C · B · B · D · C
 NATIONAL COUNCIL OF
 BUILDING DESIGNERS
 1000 K STREET, N.W.
 WASHINGTON, D.C. 20004
 (202) 462-6000

A | BD
 AMERICAN
 INSTITUTE OF
 BUILDING DESIGNERS

WWW.FDSENG.COM



FDS JOB NO.:

TO THE BEST OF THE ENGINEER'S KNOWLEDGE AND UNDERSTANDING, THE STRUCTURAL PLANS AND SPECIFICATIONS COMPLY WITH THE CURRENT FLORIDA RESIDENTIAL BUILDING CODE SHOWN AND SEALED FOR THE STRUCTURAL PORTION OF THIS DRAWING.

PARK SQUARE
HORIZONS WEST
4-UNIT - ADAMS END UNITS

project no.	2022142
checked:	
drawn:	AB
date:	05-17-22
scale:	

S2.2

NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED

RSH

ENGINEERED ROOF PER ASCE 7-16 ROOF DESIGN ALLOWABLE COMPONENTS AND CLADDING WIND PRESSURES AND SUCTIONS FOR MEAN ROOF HEIGHT ≤ 25 ft

WIND SPEED (ULTIMATE)

WIND SPEED (ALLOWABLE)

EXPOSURE CATEGORY

140.0 MPH

108.4 MPH

C

EFFECTIVE WIND AREA (50 FEET)

WIND PRESSURE AND SUCTION (PSF)

(+) VALUE DENOTES PRESSURE

(-) VALUE DENOTES SUCTION

AREA	ROOF	1	2e	2n	2i	3	3e	3r
10	HIP	-35.94	-49.57		-49.57	-49.57		
	GABLE	-38.22	-38.22	-60.99	-60.99		-60.99	-78.58

ROOF NAILING SCHEDULE/ NAILING ZONES (SHINGLE AND TILE):
ZONE 1: ASTM F1667 RSRs-01 (8d) NAILS @ 6" O.C. ON EDGE AND 6" O.C IN FIELD
ZONE 2e, 2n, 2r: ASTM F1667 RSRs-01 (8d) NAILS @ 4" O.C. ON EDGE AND 4" O.C IN FIELD
ZONE 3, 3e, 3r: ASTM F1667 RSRs-01 (8d) NAILS @ 4" O.C. ON EDGE AND 4" O.C IN FIELD
ROOF SHEATHING:
SHINGLE: 7/16" EXP. 1 (2^{1/2}) or 15/32" EXP. 1 (2^{1/2})
TILE: 15/32" EXP. 1 (2^{1/2})
NOTE:
1. PER CODE ASTM F1667 RSRs-01 REFERENCE TO 8d (2 3/8" x 0.113") NAILS
2. WHERE THE SHEATHING THICKNESS IS GREATER THAN 15/32", SHEATHING SHALL BE FASTENED WITH ASTM F1667 RSRs-03 10d (2 1/2" x 0.131") NAILS OR ASTM F1667 RSRs-04 (3" x 120") NAILS
3. GABLES- DROP GABLE END & (1) ADDITIONAL DROPPED TRUSS 2x4 #2 SYP OUTLOOKER RAFTER W/ BLOCKING @ 16" O.C. IF NO DROPPED GABLE END, ATTACH 2x4 #2 SYP BLOCKING @ 16" O.C. FIRST 4 BAYS WITH (2) 12d NAILS EA. END. ATTACH ROOF SHEATHING TO RAFTERS W/ BLOCKING PER NAILING SCHEDULE.
HIP ROOF >20 TO 27 DEG.
[4:12]-[6:12]

a=4ft

3

2e

2n

2i

3

3e

3r

a=4ft

GABLE ROOF > 20 TO 27 DEG.
[4:12]-[6:12]

SYMBOL	DESIGN DESCRIPTION
BW# 2x	INDICATES BEARING WALL. SEE BEARING WOOD BEARING SCHEDULE ON SN. SEE ARCHITECTURAL PLANS FOR WALL WIDTH, 2x4 MINIMUM U.O.N.
PSW	INDICATES PERFORATED SHEAR WALL. SEE ARCHITECTURAL PLANS FOR WALL WIDTH, 2x4 MINIMUM U.O.N.
C#	INDICATES BUILT UP COLUMN. SEE FRAMING PLAN FOR SIZE. DETAIL WF37/SN FOR PLY ATTACHMENT AND UPLIFT CONNECTION SCHEDULE ON SN FOR CONNECTION TO SLAB
C#*	INDICATES NO BOTTOM CONNECTOR REQUIRED
#	INDICATES UPLIFT CONNECTION CONSTRUCTED PER DETAIL UPLIFT CONNECTOR SCHEDULE ON SHEET SN
#	INDICATES WINDOW PRESSURE - SEE S0 FOR MORE INFORMATION.
	INDICATES LINTEL PER LINTEL PLAN

FRAMING NOTES:

- SEE WIND SPEED CHART ON S0 FOR WINDOW PRESSURES
- AT SECOND FLOOR FOR TYPICAL CORNER FRAMING SEE DETAIL FB06/D3

GENERAL NOTES:

- THE FRAMING PLAN SHOWN INDICATES THE "TRUSS SYSTEM" AND IS THE RESPONSIBILITY OF THE TRUSS SYSTEM ENGINEER (DESIGN PROFESSIONAL OF RECORD). THE TRUSS DESIGN ENGINEER (DELEGATED ENGINEER) HAS FINAL, RESONSIBILITY FOR EACH INDIVIDUAL TRUSS AND TRUSS PROFILE, AND IS TO SUBMIT A FINAL SET OF TRUSS ENGINEERING SIGNED AND SEALED TRUSS DRAWINGS TO DESIGN PROFESSIONAL OF RECORD FOR REVIEW PRIOR TO FABRICATION
- ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES WITH IN THIS PLAN SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN PROFESSIONAL FOR CLARIFICATION PRIOR TO CONSTRUCTION.
- SEE SHEET SN FOR DESIGN SCHEDULES AND NOTES: FOUNDATION SCHEDULE / COLUMN SCHEDULE / BEARING WALL SCHEDULE / BEAM SCHEDULE / HEADER SCHEDULE / CONNECTION SCHEDULE / FLOOR AND ROOF NOTES.

PLAN KEY NOTES

1 SEE DETAIL WS18/D3 FOR RAISED HEEL TYP. U.O.N.

BUILDER NOTE:

TRUSS LAYOUT, CONNECTORS & ENGINEERING BASED ON TRUSSES PROVIDED BY A-1 INDUSTRIES, PROJECT NAME CPSM4 w/ TRUSS DESIGN DATED 4/24/23 IF THE TRUSS LAYOUT SHOWN DOES NOT MATCH THE TRUSS MANUFACTURERS LAYOUT AND DATE ABOVE

-----STOP-----

AND CALL THE ENGINEER OF RECORD PRIOR TO PLACEMENT OF ANY TRUSSES.

SYMBOL	DESIGN DESCRIPTION
	2x. INTERIOR BEARING SHEARWALL - SEE BEARING WALL SCHEDULE ON SHEET SN FOR REQUIREMENTS.
	INDICATES BEARING WALL. SEE BEARING WOOD BEARING SCHEDULE ON SN
	2x WOOD FRAME WALL @ 9'-0"

KEY PLAN

ROOF FRAMING PLAN

SCALE: 1/4" = 1'-0"

B&A Design Studio, Inc.

4017 W. 1st Street
Sanford, FL 32771
ph: 407 829 8900
fax: 407 829 2040
www.badesignstudios.com

N.C.B.D.C.

A.I. AMERICAN INSTITUTE OF BUILDING DESIGN

FDS

ENGINEERING ASSOCIATES
288 Southhall Lane, Suite 200, Maitland, FL 32751
Phone: 407-829-8900
Fax: 407-829-2040
Email: info@fdseng.com
Certificate of Authorization No. 39161
□ CARL A. BROWN, PE, FL #5628
□ SCOTT LEWIS, PE, FL #79790
DATE: November 9, 2023
THIS SEAL IS THE PROPERTY OF THE ENGINEER AND SHALL REMAIN IN HIS OR HER POSSESSION. IT IS TO BE USED ONLY FOR THE STRUCTURAL DESIGN OF THE DRAWING.

PARK SQUARE
HORIZONS WEST
4-UNIT - ADAMS END UNITS

title:

project no. 2022142
checked:
drawn: AB
date: 05-17-22
scale:

S3.1

NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED

The structural design of this building is in accordance with the FLORIDA BUILDING CODE 7TH EDITION (2020) RESIDENTIAL and is certified as such.

RSH

ENGINEERED ROOF PER ASCE 7-16 ROOF DESIGN ALLOWABLE COMPONENTS AND CLADDING WIND PRESSURES AND SUCTIONS FOR MEAN ROOF HEIGHT ≤ 25 ft

WIND SPEED (ULTIMATE)

WIND SPEED (ALLOWABLE)

EXPOSURE CATEGORY

140.0 MPH

108.4 MPH

C

EFFECTIVE WIND AREA (SQ FEET)

WIND PRESSURE AND SUCTION (PSF)

(+) VALUE DENOTES PRESSURE

(-) VALUE DENOTES SUCTION

AREA	ROOF	1	2e	2n	2r	3	3e	3r
10	HIP	-35.94	-49.57		-49.57	-49.57		
	GABLE	-38.22	-38.22	-60.99	-60.99		-60.99	-78.58

ROOF NAILING SCHEDULE/ NAILING ZONES (SHINGLE AND TILE):

ZONE 1:

ASTM F1667 RSR-01 (8d) NAILS @ 6" O.C. ON EDGE AND 6" O.C. IN FIELD

ZONE 2e, 2n, 2r:

ASTM F1667 RSR-01 (8d) NAILS @ 4" O.C. ON EDGE AND 4" O.C. IN FIELD

ZONE 3, 3e, 3r:

ASTM F1667 RSR-01 (8d) NAILS @ 4" O.C. ON EDGE AND 4" O.C. IN FIELD

ROOF SHEATHING:

SHINGLE: 7/16" EXP. 1 (2¹/₂)^(a) or 1¹/₂" EXP. 1 (2¹/₂)^(a)

TILE:

1¹/₂" EXP. 1 (2¹/₂)^(a)

NOTE:

1.

PER CODE ASTM F1667 RSR-01 REFERENCE TO 8d (2 3/8" x 0.113") NAILS

2.

WHERE THE SHEATHING THICKNESS IS GREATER THAN 1¹/₂", SHEATHING SHALL BE FASTENED WITH ASTM F1667 RSR-03 10d (2 1/2" x 0.131") NAILS OR ASTM F1667 RSR-04 (3" x 120") NAILS

3.

GABLES- DROP GABLE END & (1) ADDITIONAL DROPPED TRUSS 2x4 #2 SYP OUTLOOKER RAFTER W/ BLOCKING @ 16" O.C. IF NO DROPPED GABLE END, ATTACH 2x4 #2 SYP BLOCKING @ 16" O.C. FIRST 4 BAYS WITH (2) 12d NAILS EA. END. ATTACH ROOF SHEATHING TO RAFTERS W/ BLOCKING PER NAILING SCHEDULE.

HIP ROOF >20 TO 27 DEG.

[4:12]-[6:12]

a=4ft

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24

25

26

27

28

29

30

31

32

33

34

35

36

37

38

39

40

41

42

43

44

45

46

47

48

49

50

51

52

53

54

55

56

57

58

59

60

61

62

63

64

65

66

67

68

69

70

71

72

73

74

75

76

77

78

79

80

81

82

83

84

85

86

87

88

89

90

91

92

93

94

95








96

97

98

99

100

SYMBOL	DESIGN DESCRIPTION
	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN , SEE ARCHITECTURAL PLANS FOR WALL WIDTH, 2x4 MINIMUM U.O.N.
	INDICATES PERFORATED SHEAR WALL, SEE ARCHITECTURAL PLANS FOR WALL WIDTH, 2x4 MINIMUM U.O.N.
	INDICATES BUILT UP COLUMN, SEE FRAMING PLAN FOR SIZE, DETAIL WF37/SN FOR PLY ATTACHMENT AND UPLIFT CONNECTION SCHEDULE ON SN FOR CONNECTION TO SLAB
	INDICATES NO BOTTOM CONNECTOR REQUIRED
	INDICATES UPLIFT CONNECTION CONSTRUCTED PER DETAIL UPLIFT CONNECTOR SCHEDULE ON SHEET SN
	INDICATES WINDOW PRESSURE - SEE S0 FOR MORE INFORMATION.
	INDICATES LINTEL PER LINTEL PLAN

FRAMING NOTES:

- SEE WIND SPEED CHART ON S0 FOR WINDOW PRESSURES
- AT SECOND FLOOR FOR TYPICAL CORNER FRAMING SEE DETAIL FB06/D3

GENERAL NOTES:

- THE FRAMING PLAN SHOWN INDICATES THE "TRUSS SYSTEM" AND IS THE RESPONSIBILITY OF THE TRUSS SYSTEM ENGINEER (DESIGN PROFESSIONAL OF RECORD). THE TRUSS DESIGN ENGINEER (DELEGATED ENGINEER) HAS FINAL, RESONSIBILITY FOR EACH INDIVIDUAL TRUSS AND TRUSS PROFILE, AND IS TO SUBMIT A FINAL SET OF TRUSS ENGINEERING SIGNED AND SEALED TRUSS DRAWINGS TO DESIGN PROFESSIONAL OF RECORD FOR REVIEW PRIOR TO FABRICATION
- ANY DISCREPANCY OR ERROR IN DIMENSIONS OR NOTES WITHIN THIS PLAN SHALL BE BROUGHT TO THE ATTENTION OF THE DESIGN PROFESSIONAL FOR CLARIFICATION PRIOR TO CONSTRUCTION.
- SEE SHEET SN FOR DESIGN SCHEDULES AND NOTES: FOUNDATION SCHEDULE / COLUMN SCHEDULE / BEARING WALL SCHEDULE / BEAM SCHEDULE / HEADER SCHEDULE / CONNECTION SCHEDULE / FLOOR AND ROOF NOTES.

PLAN KEY NOTES




1 SEE DETAIL WS18/D3 FOR RAISED HEEL TYP. U.N.O.

BUILDER NOTE:

TRUSS LAYOUT, CONNECTORS & ENGINEERING BASED ON TRUSSES PROVIDED BY A-1 INDUSTRIES, PROJECT NAME CP5M14 w/ TRUSS DESIGN DATED 4/24/23 IF THE TRUSS LAYOUT SHOWN DOES NOT MATCH THE TRUSS MANUFACTURERS LAYOUT AND DATE ABOVE

---STOP---

AND CALL THE ENGINEER OF RECORD PRIOR TO PLACEMENT OF ANY TRUSSES.


SYMBOL	DESIGN DESCRIPTION
	2x. INTERIOR BEARING SHEARWALL - SEE BEARING WALL SCHEDULE ON SHEET SN FOR REQUIREMENTS.
	INDICATES BEARING WALL SEE BEARING WOOD BEARING SCHEDULE ON SN
	2x WOOD FRAME WALL @ 9'-0"

KEY PLAN

ROOF FRAMING PLAN


SCALE: 1/4" = 1'-0"

B&A Design Studio, Inc.



4017 W. 1st Street
Sanford, FL 32771
ph: 407 820 8900
fax: 407 820 2040
www.badesignstudios.com

N.C.B.D.C.



A.I. AMERICAN INSTITUTE OF BUILDING DESIGN

WWW.FDSIENG.COM

FDSI

ENGINEERING ASSOCIATES

288 Southhall Lane, Suite 200, Maitland, FL 32751
Phone: 407.820.8900
Fax: 407.820.2040
Certificate of Authorization No. 9161

- ☐ CARL A. BROWN, PE - FL #5628
- ☐ SCOTT LEWIS, PE - FL #79790
- ☐ DATE: November 9, 2023

THIS SET OF DRAWINGS IS THE PROPERTY OF B&A DESIGN STUDIO, INC. AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT THE WRITTEN PERMISSION OF B&A DESIGN STUDIO, INC.

FDSI JOB NO.:

PARK SQUARE
HORIZONS WEST
4-UNIT - ADAMS END UNITS

title:


project no. 2022142
checked:
drawn: AB
date: 05-17-22
scale:

S3.2

The structural design of this building is in accordance with the FLORIDA BUILDING CODE 7TH EDITION (2020) RESIDENTIAL and is certified as such.

NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED

APPROVED LINTEL MANUFACTURERS: CASTE-CRETE, QUALITY AND LOTTS



TYPICAL LINTEL DETAIL	TYPE DESIGNATION
-----------------------	------------------

MARK	LINTEL DESIGN	MARK	LINTEL DESIGN	MARK	LINTEL DESIGN
(A)	8RF6-0B/1T	(H)	8RF30-1B/1T	(Q)	8RF30-0B/1T
(B)	8F8-0B/1T	(J)	8F32-1B/1T	(R)	8F32-0B/1T
(C)	8RF14-1B/1T	(K)	8RF14-0B/1T	(S)	8F28-1B/1T
(D)	8F16-1B/1T	(L)	8F16-0B/1T	(T)	8F40-1B/1T
(E)	8F20-1B/1T	(M)	8F20-0B/1T	(U)	8F16-2B/2T
(F)	8RF22-1B/1T	(N)	8RF22-0B/1T	(V)	8F12-1B/1T
(G)	8F24-1B/1T	(P)	8F24-0B/1T		

GENERAL INSTALLATION NOTES

1. PROVIDE FULL MORTAR HEAD AND BED JOINTS.
2. SHAPE FILL JOINTS ARE REQUIRED
3. INSTALLATION OF LINTEL MUST COMPLY w/ THE ARCHITECTURAL AND STRUCTURAL DRAWINGS
4. U-LINTELS ARE LOCATED MANUFACTURED w/ 5/8" LONG NOTCHES AT THE END TO ACCOMMODATE VERTICAL CLAY REINFORCING AND GROUTING.
5. U-LINTEL #8 OR 10 REINFORCING VERTICAL DEFLECTION, EXCEPT LINTELS 17" AND LONGER w/ NOMINAL HEIGHT OF 8" MEET OR EXCEED 1/80
6. BOTTOM FIELD ADDED REBAR TO BE LOCATED AT THE BOTTOM OF THE LINTEL CAVITY
7. 3/8" WIRE STIRRUPS ARE WELDED TO THE BOTTOM STEEL FOR MECHANICAL ANCHORAGE
8. CAST-IN-PLACE CONC. MAY BE PROVIDED IN COMPOSITE LINTELS IN LIEU OF CMU
9. SAFE LOAD RATING BASED ON RATIONAL DESIGN ANALYSIS PER ACI 318 AND ACI 530R
10. EXTERIOR SURFACES OF LINTELS SHALL BE FINISHED TO MATCH EXTERIOR SURFACES OF CMU
11. THE EXTERIOR SURFACE OF LINTELS INSTALLED IN EXTERIOR CONCRETE MASONRY WALLS SHALL HAVE A COATING OF STUCCO APPLIED IN ACCORDANCE WITH ASTM C-926 OR OTHER APPROVED COATING
12. LINTELS INSTALLED SIMULTANEOUSLY VERTICAL (GRAVITY AND UPLIFT) AND HORIZONTAL (LATERAL) LOADS SHOULD BE FOR COMBINE LOADING WITH THE FOLLOWING EQUATIONS:


$$\frac{\text{APPLIED VERTICAL LOAD}}{\text{SAFE VERTICAL LOAD}} + \frac{\text{APPLIED HORIZONTAL LOAD}}{\text{SAFE HORIZONTAL LOAD}} \leq 1.0$$

GENERAL MATERIAL NOTES:


1. fc PRECAST LINTEL = 3500 P.S.I.
2. fc PRESTRESSED LINTEL = 6000 P.S.I.
3. GROUTED PER ASCM C476 fg = 3000 P.S.I. w/ MAX $\frac{3}{4}$ " AGGREGATE AND 8" TO 11" SUMMIT
4. CMJU PER ASTM C90 w/ MIN NET AREA COMPRESSION STRENGTH = 2000 P.S.I
5. REBAR PER ASTM A615 GRADE 60
6. 270 LOW RELAXATION $\frac{7}{8}$ " WIRE PER ASTM A510
7. MORTAR PER ASTM C270 TYPE M OR S

GENERAL LINTEL NOTES


1. AREAS OF BLOCK ABUT. MASONRY OPENINGS ARE TO BE GROUTED SOLID TO THE BEAM.
2. REBAR IN THE BEAM IS TO BE CONT. THROUGH OUT INCLUDING ABUT. MASONRY OPENINGS. U.N.O.
3. ALL STANDARD LINTELS TO HAVE MIN. 4" BEARING EACH END BASED ON CAST CRETE JOISTS AND QUALITY LINTEL SPECS.
4. LINTEL MINIMUM DEPTHS ARE CALLED OUT ON LINTEL PLAN. IF CONTRACTOR INSTALLS A DEEPER LINTEL THAN INDICATED ON THE PLAN, THE EXCESS DEPTHS BECAUSE OF THE DEPTHS OF THE JOIST OR CHAIRS SHALL BE INDICATED BY A LETTER IF (I) ANY LINTEL IS INSTALLED CONTACT EOR FOR APPROVAL.
5. IF A DEEPER LINTEL IS REQUIRED FOR A MINIMUM OF 3" AS A MIN. 32" FOR HEAD CONDITIONS. IF LINTEL GREATER THAN 32" HAS A GREATER CAPACITY AND THEREFORE IS ADEQUATE FOR THE LOADS.
6. G.C. TO VERIFY ALL LINTEL DIMENSIONS IN FIELD. DIMENSIONS SHOWN ARE CLEAR SPAN ONLY.








DBL LINTEL @ TRANSOM
SCALE: 3/4" = 1'-0"




8F12-1B/1T




MS23 90 DEGREE CORNER DETAIL
SCALE: 3/4" = 1'-0"


WALL TYPE	
SYMBOL	DESIGN DESCRIPTION
	2x INTERIOR BEARING SHEARWALL - SEE BEARING WALL SCHEDULE ON SHEET SN FOR REQUIREMENTS.
	INDICATES BEARING WALL. SEE BEARING WOOD BEARING SCHEDULE ON SN
	MASONRY WALL TOP @ 9'-4"
	MASONRY WALL TOP @ 10'-8" ABV. GRADE
	MASONRY WALL TOP @ 10'-8" ABV. GRADE



(MS05) TYP. REBAR SPLICE
SCALE: 3/4" = 1'-0"




WF01 **MASONRY ARCH FRAMING**
SCALE: 3/4" = 1'-0"



MS12 GARAGE DOOR INSTALLATION
SCALE: 3/4" = 1'-0"

LINTEL MINIMUM DEPTHS ARE CALLED OUT ON LINTEL PLAN. IF CONTRACTOR INSTALLS A DEEPER LINTEL THAN INDICATED ON THE PLAN, DOING THIS INCREASES THE STRENGTH OF THE LINTEL AND IS APPROVED WITHOUT ENGINEERING LETTER. IF A SMALLER LINTEL IS INSTALLED CONTACT EOR FOR APPROVAL (SEE SHEET L1 FOR LINTEL SCHEDULE).




LINTEL PLAN


SCALE: 1/8" = 1'-0"

ATTACHMENT REQUIREMENTS			
SIZE	TAPCONS	SPACING	# ROWS
2 x 4	3/16" X 3"	12" O.C.	1
2 x 6	3/16" X 3"	12" O.C.	2
2 x 8	3/16" X 3"	12" O.C.	2

- NOTES:
1. TAPCONS TO BE 6" FROM END
 2. FASTENING TO WINDOW TO BUCK RESPONSIBILITY OF WINDOW MANUFACTURER
 3. 1x BUCKS ARE NOT STRUCTURAL AND SHALL BE USED ONLY AS BLOCKING



MS11 MASONRY BUCK INSTALLATION
SCALE: 3/4" = 1'-0"



MS03 MASONRY TO WD BRG WALL
SCALE: 3/4" = 1'-0"

© 2020 B&A DESIGN STUDIO, INC. RESERVES COPYRIGHT & OTHER RIGHTS RESTRICTING THESE DOCUMENTS TO THE ORIGINAL SITE OR PURPOSE FOR WHICH THEY WERE PREPARED. REPRODUCTIONS, CHANGES OR ASSIGNMENTS ARE PROHIBITED.



**B&A Design
Studio,
Inc.**

4017 W. 1st Street
Sanford, FL. 32771
ph 407 829 8900
fax 407 829 2040
www.badesignstudios.com

N-C-B-D-C

NATIONAL COUNCIL OF BUILDING DESIGN

AMERICAN INSTITUTE OF BUILDING DESIGN

WWW.FDSENG.COM



O: 321-972-0491 F: 407-880-2304
Certificate of Authorization No. 9161
☐ CARLA A. BROWN, PE - FL # 56126
☐ SCOTT LEVKOWSKI, PE - FL # 78750
☐

DATE: November 9, 2023

TO THE BEST OF THE ENGINEER'S KNOWLEDGE AND UNDERSTANDING, THE STRUCTURAL PLANS SPECIFICALLY COMPLY WITH THE CURRENT FLORIDA RESIDENTIAL BUILDING CODE, SIGNED AND

DATE: November 9, 2023

FDS JOB NO.




PARK SQUARE
HORIZONS WEST
4-UNIT - ADAMS END UNITS

title:

project no. 2022142
checked:
drawn: AB
date: 05-17-22
scale:

L1

NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED



SD02 GENERAL STAIR SECTIONS & PLAN
SCALE: 3/4"=1'-0"

CAST CRETE OR QUALITY/ LOTTS LINTEL LOAD SPECIFICATIONS

SAFE GRAVITY LOADS FOR 8" PRECAST & PRESTRESSED U-LINTELS








LENG.T.H	TYPE	SAFE LOAD - POUNDS PER LINEAR FOOT	SAFE GRAVITY LOADS FOR 8" PRECAST & PRESTRESSED U-LINTELS							
			8F8-08	8F12-08	8F16-08	8F20-08	8F24-08	8F28-08	8F32-08	8F36-08
2'-10" (34")	PRECAST	2231	3069	4605	6113	7547	8974	10394	11809	13224
3'-6" (42")	PRECAST	2231	3069	4605	6113	7547	8974	10394	11809	13224
4'-0" (48")	PRECAST	1966	2561	2751	3820	4890	5961	7034	8107	9180
4'-6" (54")	PRECAST	1599	2189	2379	3448	4518	5589	6661	7734	8807
5'-4" (64")	PRECAST	1217	1349	1438	1999	2560	3123	3686	4249	4812
5'-10" (70")	PRECAST	1062	1105	1173	1631	2090	2549	3009	3470	3931
6'-6" (78")	PRECAST	908	1238	2177	3480	5381	8360	10394	12428	14462
7'-6" (90")	PRECAST	743	1011	1729	2632	2205	2698	3191	3685	4179
9'-4" (112")	PRECAST	554	699	1160	1625	2564	3486	4408	5330	6252
10'-6" (126")	PRECAST	475	535	890	1247	2093	2777	3461	4145	4829
11'-4" (136")	PRECAST	362	582	945	1366	1846	2423	3127	3831	4535
12'-0" (144")	PRECAST	337	540	873	1254	1684	2193	2805	3510	4214
13'-4" (160")	PRECAST	296	471	755	1075	1428	1838	2316	2883	3450
14'-0" (168")	PRECAST	279	424	706	1002	1326	1697	2127	2630	3133
14'-8" (176")	PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR	NR
15'-4" (184")	PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR	NR
17'-4" (208")	PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR	NR
19'-4" (232")	PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR	NR
21'-4" (256")	PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR	NR
22'-0" (264")	PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR	NR
24'-0" (288")	PRESTRESSED	N.R.	NR	NR	NR	NR	NR	NR	NR	NR

(#) THE NUMBERS IN PARENTHESIS ARE PERCENT REDUCTIONS FOR GR40 FIELD ADDED REBAR.

SAFE UPLIFT LOADS FOR 8" PRECAST & PRESTRESSED U-LINTELS

LENG.T.H	TYPE	SAFE UPLIFT LOADS FOR 8" PRECAST & PRESTRESSED U-LINTELS							
		8F8-11	8F12-11	8F16-11	8F20-11	8F24-11	8F28-11	8F32-11	8F36-11
2'-10" (34")	PRECAST	1972	3173	4460	5747	7034	8321	9608	10895
3'-6" (42")	PRECAST	1569	2524	3547	4569	5591	6613	7636	8658
4'-0" (48")	PRECAST	1363	2192	3079	3966	4853	5740	6627	7514
4'-6" (54")	PRECAST	1207	1940	2724	3508	4292	5077	5861	6645
5'-4" (64")	PRECAST	1016	1632	2290	2949	3607	4265	4924	5582
5'-10" (70")	PRECAST	909	1492	2093	2694	3295	3897	4498	5099
6'-6" (78")	PRECAST	835	1340	1880	2419	2959	3498	4038	4578
7'-6" (90")	PRECAST	727	1166	1634	2102	2571	3039	3508	3977
9'-4" (112")	PRECAST	591	680	1133	1471	1811	2152	2494	2835
10'-6" (126")	PRECAST	530	552	914	1185	1458	1732	2007	2281
11'-4" (136")	PRECAST	494	599	1028	1422	1738	2053	2369	2684
12'-0" (144")	PRECAST	470	441	723	936	1151	1366	1582	1797
13'-4" (160")	PRECAST	428	455	770	1145	1444	1718	1993	2267
14'-0" (168")	PRECAST	384	346	559	723	887	1052	1218	1384
14'-8" (176")	PRESTRESSED	246	390	655	968	1324	1625	1926	2227
15'-4" (184")	PRESTRESSED	224	302	485	626	767	909	1052	1194
17'-4" (208")	PRESTRESSED	187	255	404	520	637	754	872	989
19'-4" (232")	PRESTRESSED	162	222	347	446	546	646	746	846
21'-4" (256")	PRESTRESSED	142	198	306	393	480	567	654	741
22'-0" (264")	PRESTRESSED	137	192	295	378	461	545	629	712
24'-0" (288")	PRESTRESSED	124	175	267	341	416	491	566	641

(#) THE NUMBERS IN PARENTHESIS ARE PERCENT REDUCTIONS FOR GR40 FIELD ADDED REBAR.




FOUNDATION SCHEDULE				
MARK	SIZE	DEPTH	REINFORCING	GRAVITY CAP. [lbs]
F1.5	1'-6" x 1'-6"	1'-0"	(2) #5 E.W. BOT.	3500
F2.0	2'-6" x 2'-0"	1'-0"	(3) #5 E.W. BOT.	7200
F2.5	2'-6" x 2'-6"	1'-0"	(3) #5 E.W. BOT.	11000
F3.0	3'-0" x 3'-0"	1'-0"	(4) #5 E.W. BOT.	15600
F3.5	3'-6" x 3'-6"	1'-0"	(4) #5 E.W. BOT.	21500
F4.0	4'-0" x 4'-0"	1'-0"	(5) #5 E.W. BOT.	28000
F4.5	4'-6" x 4'-6"	1'-4"	(5) #5 E.W. BOT.	34500
F5.0	5'-0" x 5'-0"	1'-4"	(6) #5 E.W. BOT.	42500
F6.0	6'-0" x 6'-0"	1'-6"	(8) #5 E.W. BOT.	

FOUNDATION DEPTH NOTE:
 • INTERIOR PAD DEPTHS AS LISTED IN THE SCHEDULE ARE THE TOTAL DEPTH AND MEASURED FROM THE TOP OF THE SLAB.
 • EXTERIOR PAD DEPTHS AS LISTED IN THE SCHEDULE ARE TOTAL DEPTH WITH THE BOTTOM OF THE FOOTING TO MATCH THE BOTTOM OF THE CONTINUOUS MONOLITHIC POUR WHICH RUNS THROUGH IT.

GENERAL FOUNDATION NOTES:
 1. PROVIDE MIN. 6 MIL. APPROVED VAPOR BARRIER. ALL JOINTS TO BE LAPPED MIN. 6" AND SEALED.
 2. 4" 2500 PSI CONC. SLAB WITH W1:4XW1.4 OVER 6 MIL. VISQUEEN VAPOR BARRIER & TREATED FOR TERMITES.
 3. GC/ BUILDER, SEE ARCH PLANS FOR ROUGH OPENING LOCATIONS AND ADDITIONAL INFORMATION REQUIRED FOR DOOR/WINDOW.
 4. INSTALLATION ALONG W/ DIMENSIONS NOT SHOWN ON FOUNDATION CONSULT W/ MANUFACTURER SPECIFICATIONS FOR POURING OR RECESSING DOOR SILLS OR SLIDING GLASS DOOR SILLS.
 5. NO WOOD STAKES PERMITTED IN FOUNDATION.
 6. PENDING SITE CONDITIONS, FOUNDATION MAY HAVE TO BE STEPPED DOWN. SEE **FM1801** FOR ADDITIONAL INFORMATION. G.C. TO DETERMINE STEP LOCATIONS, IF REQUIRED.
 7. STEEL BENDS AND LAP SPICE SEE **FM1801** AND **FM19D1**.
 8. ALL EQUIPMENT AND/OR APPLIANCES HAVING AN IGNITION SOURCE SHALL BE ELEVATED A MIN OF 18". CONTRACTOR TO PROVIDE SUCH PLATFORM W/ EITHER MASONRY OR WOOD CONSTRUCTION.
 9. ASSUMED ALLOWABLE SOIL BEARING PRESSURE AFTER COMPACTION: 2000 PSF (SEE SOIL REPORTS AND SPECIFICATIONS FOR COMPACTION REQUIREMENTS). IF SOIL CONDITIONS ON THE PROJECT DO NOT MEET OR EXCEED THE CAPACITY, THE GENERAL CONTRACTOR SHALL CONTACT THE ENGINEER PRIOR TO FOUNDATION POUR FOR VERIFICATION OF FOUNDATION DESIGN. SOIL TO BE FREE OF ORGANIC MATERIAL AND COHESIVE SOILS. COMPACTION IN 12" LIFTS TO AT LEAST 95% OF MAX. DRY DENSITY AS DETERMINED BY ASTM D 1557 (MODIFIED PROCTOR).
 10. R-403 1/4 MINIMUM DEPTH EXTERIOR FOOTINGS SHALL BE PLACED NOT LESS THAN 12 INCHES (305mm) BELOW THE FINISHED GRADE OF GROUND SURFACE.

COLUMN SCHEDULE				
MARK	COLUMN SIZE	FIRST FLOOR BASE CONNECTIONS, SEE PLAN FOR SECOND FLOOR CONNECTIONS	UPLIFT(lb)	
C1	(3) 2x #2 SPF	(4)12d TOENAILS	NO UPLIFT	
C2	(3) 2x #2 SPF	DTT22 W/ 1/2" ATR & (8) 3/4" x 1 1/2" SDS SCREWS	1835	
C3	(3) 2x #2 SPF	(4)12d TOENAILS	NO UPLIFT	
C4	(3) 2x #2 SPF	DTT22 W/ 1/2" ATR & (8) 3/4" x 1 1/2" SDS SCREWS	1835	
C5	4x4 P.T.#2 SYP POST	ABU44 w/ 1/2" ATR & (12)16d NAILS FIRST/SECOND FLOOR CONN.	G = 6665 U = 1782	
C6	6x6 P.T.#2 SYP POST	ABU66 w/ 1/2" ATR & (12)16d NAILS FIRST/SECOND FLOOR CONN.	G = 12000 U = 2070	
C7	8x8 P.T.#2 SYP POST	ABU88 w/2 1/2" ATR & (18)16d NAILS FIRST/SECOND FLOOR CONN.	G = 24335 U = 2088	
C8	3.5" x 3.5" P.L. 1.8E Fb=2400 PSI (W/ MANUFACTURED EXT.)	HDU5-SDS2.5 w/ 7/8" ATR AND (14) 1/2"x2 1/2" SDS WOOD SCREWS	5080	
C9	3.5" x 2.5" P.L. 1.8E Fb=2400 PSI (W/ MANUFACTURED EXT.)	HDU5-SDS2.5 w/ 7/8" ATR AND (14) 1/2"x2 1/2" SDS WOOD SCREWS	5080	
C10	3.5" x 7" P.L. 1.8E Fb=2400 PSI (W/ MANUFACTURED EXT.)	HDU8-SDS2.5 w/ 7/8" ATR AND (20) 1/2"x2 1/2" SDS WOOD SCREWS	6372	
C11	6.25" x 5.25" P.L. 1.8E Fb=2400 PSI (W/ MANUFACTURED EXT.)	HDU8-SDS2.5 w/ 7/8" ATR AND (20) 1/2"x2 1/2" SDS WOOD SCREWS	7082	


GENERAL COLUMN NOTES:
 1. ALL STRUCTURAL LUMBER TO BE SYP#2 OR SPF#2 UNO ON PLAN.
 2. MINIMUM BLOCK EMBEDMENT: 5" EMBEDMENT FOR 1/2" ATR. 6" EMBEDMENT FOR 5/8" ATR. 8" EMBEDMENT FOR 7/8" ATR.
 3. P.L. COL. TO BRG DIRECTLY ON FOUNDATION. CUT BASE PLATE AS REQ'D. G.C. TO PROVIDE MOISTURE BARRIER.
 4. IF COL. IS CALLED OUT ON 2ND FLOOR, THE BASE CONNECTION IS NOT REQ'D. SEE PLANS FOR BASE CONNECTION.
 5. VALUES HAVE BEEN REDUCED FOR NARROW FACE APPLICATION. CONNECTIONS SHALL BE INSTALLED ON NARROW OR WIDE FACE PER SIMPSON TC-SCLCLM



WF17 TOP PLATE SPLICE SCALE: 3/4" = 1'-0"


WOOD BEARING WALL SCHEDULE				
MARK	STUD SPACING	CONNECTION & FASTENERS	LUMBER SPECIES	UPLIFT CAP. [lb]
BW1	16"	(2)16d TOENAILS OR (2)12d END OR BOX NAILS	#2 SPF	NO UPLIFT
BW2	16"	SP2 w/ (6)10d NAILS	SP1 w/ (6) 10d NAILS & ANCHOR BOLTS	#2 SPF 402
BW3	16"	(2) SP2 w/ (6)10d NAILS	SP1 w/ (6) 10d NAILS & ANCHOR BOLTS	#2 SPF 804
BW4	16"	(2)16d TOENAILS	(3) 12d TOENAILS OR (2) 12d END OR BOX NAILS	#2 SYP NO UPLIFT
BW5	16"	SP2 w/ (6)10d NAILS	SP1 w/ (6) 10d NAILS & ANCHOR BOLTS	#2 SYP 439
BW6	16"	(2) SP2 w/ (6)10d NAILS	SP1 w/ (6) 10d NAILS & ANCHOR BOLTS	#2 SYP 878
BW7	12"	(2)16d TOENAILS	(3) 12d TOENAILS OR (2) 12d END OR BOX NAILS	#2 SPF NO UPLIFT
BW8	12"	SP2 w/ (6)10d NAILS	SP1 w/ (6) 10d NAILS & ANCHOR BOLTS	#2 SPF 535
BW9	12"	(2) SP2 w/ (6)10d NAILS	SP1 w/ (6) 10d NAILS & ANCHOR BOLTS	#2 SPF 1070
BW10	12"	(2)16d TOENAILS	(3) 12d TOENAILS OR (2) 12d END OR BOX NAILS	#2 SYP NO UPLIFT
BW11	12"	SP2 w/ (6)10d NAILS	SP1 w/ (6) 10d NAILS & ANCHOR BOLTS	#2 SYP 585
BW12	12"	(2) SP2 w/ (6)10d NAILS	SP1 w/ (6) 10d NAILS & ANCHOR BOLTS	#2 SYP 1170

CROSS REFERENCE CHART
 SIMPSON SP1 / USP SP22 SIMPSON SP2 / USP SPT24
 (2) 2x HEADER (U.N.O.) SEE FLOOR PLAN FOR MIN. SIZE. SEE HD/SN FOR CONNECTION INFO. IF HEADER IS WITHIN A WALL, NO UPLIFT AS INDICATED IN THE WOOD BEARING WALL SCHEDULE, THE CONNECTORS INDICATED IN WF09 & HD CAN BE IGNORED.




BWD BEARING WALL DETAIL SCALE: NONE

GENERAL BEARING WALL NOTES:
 1. ALL STRUCTURAL LUMBER DESIGNATED AS SYP SHALL BE SYP #2 AND ALL STRUCTURAL LUMBER DESIGNATED AS SPF SHALL BE SPF #2 U.N.O.
 2. SEE FLOOR PLAN FOR WALL SIZE. ASSUME 2x4 STUDS USED UNO.
 3. CONNECTIONS TO BE INSTALLED TO EACH STUD AS INDICATED.
 4. CONTACT E.O.R. IF SP#1s, SP#s OR SP#s CONNECTORS ARE SUBSTITUTED, TO VERIFY THEY MEET THE STRUCTURAL REQUIREMENTS.
 5. IF "BW" IS INDICATED ON SECOND FLOOR BASE CONNECTION TO BE IGNORED. SEE WF06 AND FB08 OR INDICATED FOR PROPER CONNECTIONS FOR 2ND FLOOR TO FIRST FLOOR CONNECTIONS. (NOTE: THIS IS FOR 2 STORY PROJECTS ONLY)
 6. IF "SVP" IS INDICATED ON PLAN THE WALL IS CONSIDERED A SHEAR WALL AND REQUIRES MIN. 7/16" OSB / PLYWOOD W/8d NAILS @ 4" O.C. IN FIELD AND EDGE TO ONE SIDE OF WALL. U.N.O. ON PLANS.
 7. ALL 2x EXTERIOR WALLS W/ SHEATHING ATTACHED PER NAILING SCHEDULE TB13SN ACTS AS SHEAR WALLS. SEE PLAN AND WALL SECTIONS FOR STUD SPACING AND GRADE.
 8. ALL TOP PLATES AND SILL PLATES SHALL BE THE SAME SPECIES AS THE WOOD STUDS.
 9. IF THE BEARING WALL IS INDICATED WITH THE BW1, BW4, BW7, BW10, THESE WALLS ARE ONLY SUPPORTING THE FLOOR LOAD AND DO NOT HAVE UPLIFT, THE STUDS ARE TOE NAILED TO THE PLATE AND THE 2x PLATE CAN BE ATTACHED WITH HARD CASED NAILS (GUN NAILS) AND WILL NOT REQUIRE THE ANCHOR BOLT ATTACHMENT INDICATED IN THE BEARING WALL SCHEDULE.




WF18 NON-BRG INTERIOR WALL SCALE: 3/4" = 1'-0"



WF37 MULTI-PLY FASTENING SCALE: 3/4" = 1'-0"

HEADER SCHEDULE				
MARK	HEADER SIZE	HEADER NOTES		
H1	(2) 2x6 #2 SYP w/ 7/16" FLITCH PLATE	1. VERIFY W/ PLAN CORRECT LENGTH OF HEADER REQUIRED. 2. IF HEADER IS ON THE 1ST FLOOR SEE PLAN FOR BEARING WALL TYPE AND FOLLOW INSTRUCTIONS WITHIN BEARING WALL SCHEDULE FOR REQUIRED CORRECTIONS U.N.O. ON PLAN.		
H2	(2) 2x8 #2 SYP w/ 7/16" FLITCH PLATE	3. IF HEADER IS ON THE 2ND FLOOR SEE PLAN FOR INDICATED HEADER CONNECTION FOR REQUIRED CONNECTIONS.		
H3	(2) 2x10 #2 SYP w/ 7/16" FLITCH PLATE	4. ALL HEADER JACK AND KING STUDS SHALL BE FASTENED TO EACH PER DETAIL WF07SN.		
H4	(2) 1 3/4" x 11 1/4" LVL 2.0E Fb=2600	5. FASTEN ALL MULTI-PLY HEADERS TOGETHER W/ (2) ROWS 12d COMMON NAILS AT 12" O.C. OR (3) ROWS IF 2x10 OR LARGER TYP. EACH SIDE OR (2) ROWS 1 1/4" x 3 1/2" SDS WOOD SCREWS @ 16" O.C. TYP. EACH SIDE.		
H5	(2) 1 3/4" x 9 1/4" LVL 2.0E Fb=2600	6. FASTEN ALL HEADERS TO KING STUDS W/ (3) 10d TOENAILS PER SIDE.		
H6	(2) 2x10 #2 SYP w/ 1" FLITCH PLATE	7. IF HEADER IS NOT SPECIFIED CONTACT E.O.R.		

HEADER SUPPORT - NUMBER OF JACKS & STUDS REQUIRED AT OPENINGS				
OPENING SIZE	2x4 WALL	2x6 OR 2x8 WALL		
1'-0" - 3'-11"	(1)	(1)	(1)	(2)
4'-0" - 8'-11"	(2)	(2)	(2)	(4)
10'-0" - 16'-0"	(3)	(3)	(3)	(6)




NOTES:
 1. OPENINGS GREATER THAN 4'-0" PROVIDE (2) 2x SILL PLATE W/ A35 CLIPS EACH SIDE.
 2. NO TOP PLATE SPLICES SHALL OCCUR OVER OR WITHIN 2 FEET OF HEADER.
 3. HOLD DOWN CONNECTIONS NOT REQUIRED AT BEARING WALLS WITHOUT UPLIFT.

HD TYPICAL FRAMING CONNECTIONS AT OPENINGS SCALE: NONE

BEAM SCHEDULE				
MARK	BEAM SIZE	SIMPSON - CONNECTIONS	USP - CONNECTIONS	
BM1	(2) 2x8 #2 SYP w/ 3/4" OSB FLITCH PLATE	WOOD POST (2) HTS20 CMU COLUMN (2) HETA16 U.N.O. ON FRAMING PLAN	WOOD POST (2) HTS20 CMU COLUMN (2) HETA16 U.N.O. ON FRAMING PLAN	
BM2	(2) 2x10 #2 SYP w/ 3/4" OSB FLITCH PLATE	FASTEN BEAM PLY'S: 2- ROWS OF 12d @ 12" O.C. EACH SIDE, TYPICAL	FASTEN BEAM PLY'S: 2- ROWS OF 12d @ 12" O.C. EACH SIDE, TYPICAL	
BM3	(2) 2x12 #2 SYP w/ 3/4" OSB FLITCH PLATE	FASTEN BEAM PLY'S: 2- ROWS OF 12d @ 12" O.C. EACH SIDE, TYPICAL	FASTEN BEAM PLY'S: 2- ROWS OF 12d @ 12" O.C. EACH SIDE, TYPICAL	
BM4	(2) 1 1/2"x11 1/4" LVL 2.0E Fb=2600 PSI	WOOD POST (2) HTS20 CMU COLUMN (2) HETA16 U.N.O. ON FRAMING PLAN	WOOD POST (2) HTS20 CMU COLUMN (2) HETA16 U.N.O. ON FRAMING PLAN	
BM5	(2) 1 1/2"x11 1/4" LVL 2.0E Fb=2600 PSI	FASTEN BEAM PLY'S: 2- ROWS OF 1 1/2"x3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EA. SIDE	FASTEN BEAM PLY'S: 2- ROWS OF 1 1/2"x3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EA. SIDE	
BM6	(2) 1 1/2"x16 1/4" LVL 2.0E Fb=2600 PSI	FASTEN BEAM PLY'S: 2- ROWS OF 1 1/2"x3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EA. SIDE	FASTEN BEAM PLY'S: 2- ROWS OF 1 1/2"x3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EA. SIDE	
BM7	(3) 2x10 #2 SYP w/ 3/4" OSB FLITCH PLATE	FASTEN BEAM PLY'S: 2- ROWS OF 12d @ 12" O.C. EACH SIDE, TYPICAL	FASTEN BEAM PLY'S: 2- ROWS OF 12d @ 12" O.C. EACH SIDE, TYPICAL	
BM8	(3) 1 1/2"x9 1/4" LVL 2.0E Fb=2600 PSI	FASTEN BEAM PLY'S: 2- ROWS OF 1 1/2"x3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EA. SIDE	FASTEN BEAM PLY'S: 2- ROWS OF 1 1/2"x3 1/2" SDS WD SCREWS @ 16" O.C. TYP. EA. SIDE	

GENERAL BEAM NOTES:
 1. VERIFY W/ PLAN CORRECT LENGTH OF BEAMS REQUIRED (MIN 4" BEARING EACH END)
 2. SEE PLAN FOR TOP OR BOTTOM OF BEAM INDICATIONS
 3. BEAMS ARE NOT TO BE DRILLED OR NOTCHED IN ANY WAY WITHOUT WRITTEN APPROVAL FROM THE E.O.R.




WF02 WOOD FRAMED ARCH SCALE: 3/4" = 1'-0"


SIMPSON STRONG TIE (C-C-2021)				
MARK	TYPE	CONNECTOR & FASTENERS	SYP	SPF
A	FRAME TO MASONRY	HETA16 w/ (9)10d x 1 1/2" OR HETA20 w/ (9)10d x 1 1/2"	1810	
B	FRAME TO FRAME	H25A w/ (10)8d x 2-1/2" NAILS	700	615
C	FRAME TO FRAME	H10A w/ (18)10d x 1 1/2" RT162 w/ (8) 8d AT 2" PLY TRUSSES	1040	1015
D	FRAME TO FRAME	MTS12 w/ (16)10d x 1 1/2" (AT EXTERIOR LOCATION INCLUDE (3) 12d TOENAILS)	1080	930
E	FRAME TO MASONRY	MGT w/ (22)10d NAILS AND 5/8" A.T.R. w/ 12" EMBEDMENT w/ SIMPSON "SET" EPOXY	990	850
F	FRAME TO FRAME	HTS20 w/ (16)10d x 1 1/2" (AT EXTERIOR LOCATION INCLUDE (3) 12d TOENAILS)	1415	1215
F1	FRAME TO FRAME	(2) HTS20 w/ (36)10d x 1 1/2" (AT EXTERIOR LOCATION INCLUDE (6) 12d TOENAILS)	2830	2430
G	FRAME TO MASONRY	HGT-2 w/ (16)10d NAILS AND (2) 3/4" A.T.R. w/ 12" EMBEDMENT w/ SIMPSON "SET" EPOXY (HGT-3 FOR 3-PLY)	10690	10690
H	FRAME TO MASONRY / FRAME	FGTR w/ (18) 1/4" x 3" SDS WOOD SCREWS AND (2) 12" x 5" TITEN HD ANCHOR BOLTS	4725	3400
J2	FRAME TO MASONRY / FRAME	(2) LGT2 w/ (32) 16d SINKERS & (14) 1/4" x 2 1/4" TITEN TURBO (2 PLY TRUSS) OR (28) 16d SINKERS FOR FRAME (EA)	4060-M	3500-M
J3	FRAME TO MASONRY / FRAME	(2) LGT3 w/ (32) 16d SINKERS & (8) 3/8" x 5" TITEN (2 PLY TRUSS) OR (28) 16d SINKERS FOR FRAME (EA)	6570-M	4730-M
K	BEAM TO BEAM	HU410 OPT HU410 w/ (18) 16d & 3/4" WEDGE-BOLT & (10) 10d NAILS	G4250 UH1795	G4280 UH1635
L	BEAM TO MASONRY	HU410 OPT HU410 w/ (18) TITEN TURBO 1/4" x 2 3/4" (10) 10d NAILS	G4450 UH1800	
L2	BEAM TO MASONRY / FRAME	HU448 OPT HU448 w/ (6) 10d NAILS & (12) 3/16" x 1 3/4" TAPER 1/2" PLY TRUSS OR (12) 16d & (6) 10d (FOR FRAME)	G43000 UH1135	G42165 UH1135
M	FRAME TO MASONRY	(2) HETA16 OPT (2) HETA20 1-PLY w/ (10) 10d x 1 1/2" OR 2-PLY w/ (12) 16d	1920	2365
N	FRAME TO MASONRY	HTSM16 w/ (8)10d NAILS AND (4) 1/4" x 1 1/4" TITEN TURBO OR HTSM20 w/ (10)10d NAILS AND (4) 1/4" x 1 1/4" TITEN TURBO	1110	955
P	FRAME TO MASONRY	H105 w/ (8) 8d x 1 1/2" NAILS AND (2) 3/8" x 4" TITEN HD	910	785
Q	FRAME TO MASONRY	DTT22 w/ (8) 8d x 1 1/2" SDS WOOD SCREWS AND (1) 1/2" A.T.R. EPOXIED w/ SIMPSON "SET" (SEE NOTE #4)	2145	1835
R	FRAME TO MASONRY	HTT5 w/ (26) 16d x 1 1/2" NAILS AND (1) 5/8" A.T.R. EPOXIED w/ SIMPSON "SET" (SEE NOTE #4 BELOW)	4350	3740
S	FRAME TO MASONRY	HTT4 w/ (18) 16d x 1 1/2" NAILS AND (1) 5/8" A.T.R. EPOXIED w/ SIMPSON "SET" (SEE NOTE #4 BELOW)	4235	3640
T	FRAME TO FRAME	H105 w/ (24) 10d x 1 1/2" NAILS	910	785
U	FRAME TO MASONRY	HM0KT w/ (6) 1/4" x 1 1/2" SDS WOOD SCREWS & (5) 1/4" x 1 1/4" TAPCONS	760	760
V	FRAME TO MASONRY	VGT w/ (16) 1/4" x 3" SDS WOOD SCREWS & (2) 5/8" A.T.R. EPOXIED w/ SIMPSON "SET" w/ 12" MIN. EMBEDMENT	4940	3555
W	FRAME TO MASONRY	VGT w/ (16) 1/4" x 3" SDS WOOD SCREWS & (2) 5/8" A.T.R. EPOXIED w/ SIMPSON "SET" w/ 12" MIN. EMBEDMENT	7185	5170
X	FRAME TO FRAME	VGT w/ (16) 1/4" x 3" SDS WOOD SCREWS & (2) 5/8" A.T.R. EPOXIED w/ SIMPSON "SET" w/ 12" MIN. EMBEDMENT	4940	3555
Y	FRAME TO FRAME	(2) HTT5 w/ (26) 16d x 1 1/2" NAILS & (1) 5/8" A.T.R. (SEE NOTE #4)	10180	8750

GENERAL CONNECTOR NOTES:
 1. CONNECT ALL FLOOR TRUSSES TO INTERIOR BEARING WOOD WALLS / BEAMS w/ (2) 12d TOENAILS.
 2. ALL TRUSS TO TRUSS CONNECTIONS ARE PROVIDED BY TRUSS MANUFACTURER, U.N.O. ON PLAN.
 3. G.C. MAY USE EITHER SIMPSON OR USP CONNECTIONS. SEE FRAMING PLAN FOR CONNECTOR CALL OUT.
 4. FOR SINGLE PLY TRUSSES, SCALE ON FULL HEIGHT #1 2x4 TO TRUSS (2) ROWS OF 10d NAILS @ 3" O.C. STAGGERED.
 5. MINIMUM A.T.R. EMBEDMENT: 5" EMBEDMENT FOR 1/2" A.T.R. 6" EMBEDMENT FOR 5/8" A.T.R. 8" EMBEDMENT FOR 7/8" A.T.R. (IF AT STEP, DEPTH IS FROM LOWER SLAB).


A	MINIMAL CONNECTOR UNO ON FRAMING PLAN	
1.	CONNECTION FOR ALL ROOF / FLOOR TRUSSES TO MASONRY WALLS/ LINTELS/ ICF WALLS UNO ON PLAN	
2.	CONNECTION AT 24" OR 32" O.C. PENDING VERTICALS FOR ALL FLOOR TRUSSES PARALLEL TO MASONRY WALLS SEE DETAIL FB1213 FOR MORE INFORMATION	
3.	CONNECTION FOR ALL HIP JACK (CORNER) JACK TO MASONRY WALLS/ICF WALLS/ LINTELS	
4.	CONNECTION FOR ALL CONTINUOUS RIM BOARD TO TOP OF MASONRY AT 32" O.C MAX. w/ (2) AT EACH CORNER. G.C. TO VERIFY LOCATION DOES NOT CONFLICT w/ITL (IF APPLICABLE) LAYOUT	
5.	CONNECT ALL FLOOR TRUSSES TO INTERIOR BEARING WOOD WALL/BEAMS w/ (2) 12d TONAILS	
B	MINIMAL CONNECTOR UNO ON FRAMING PLAN	
1.	CONNECTION FOR JACK TRUSS TO WOOD WALL OR BEAM	
C	MINIMAL CONNECTOR UNO ON FRAMING PLAN	
1.	CONNECTION FOR ALL TRUSSES TO INTERIOR/EXTERIOR BEARING WOOD WALLS AND/OR BEAMS	




FS01 SINGLE OR 2-STORY FOOTING
SCALE: 3/4" = 1'-0"




FS02 EXTERIOR BEARING @ GARAGE
SCALE: 3/4" = 1'-0"




FS03 EXTERIOR BEARING
SCALE: 3/4" = 1'-0"




FS07 FOOTING @ GARAGE DOOR
SCALE: 3/4" = 1'-0"




FS08 INT. BRG. @ STEP DOWN
SCALE: 3/4" = 1'-0"




FS09 SECTION @ SHOWER
SCALE: 3/4" = 1'-0"




FS10 EXTERIOR BEARING @ RECESS
SCALE: 3/4" = 1'-0"




FM03 THICKENED EDGE
SCALE: 3/4" = 1'-0"




FM10 INT. BRG WALL
SCALE: 3/4" = 1'-0"




FM11 STEP DOWN BRG.
SCALE: 3/4" = 1'-0"




FM12 STEP DOWN @ NON BRG.
SCALE: 3/4" = 1'-0"




FM20 CONTROL JOINT
SCALE: 3/4" = 1'-0"




FM19 TYP. CORNER BAR DETAIL
SCALE: 3/4" = 1'-0"




FM18 TYP. STEP FOOTING DETAIL
SCALE: 3/4" = 1'-0"



FS16 LARGE STEP DOWN
SCALE: 3/4" = 1'-0"




SITE WALL SCHEDULE					
SITE WALL HEIGHT (h)	FOOTING SIZE WIDTH	FOOTING SIZE DEPTH	NUMBER/SIZE OF BARS	MAXIMUM DOWEL SPACING	
0'-0" - 2'-8"	2'-0"	1'-0"	w/ (3) #5 CONT.	#5 @ 72" O.C.	
>2'-8" - 5'-0"	3'-0"	1'-0"	w/ (3) #5 CONT.	#5 @ 48" O.C.	
>5'-0" - 7'-0"	3'-4"	1'-0"	w/ (5) #5 CONT.	#5 @ 24" O.C.	
>7'-0" - 8'-0"	4'-0"	1'-4"	w/ (5) #5 CONT. & #5 @ 32" O.C. TRANSV.	#6 @ 24" O.C.	




- CONTROL JOINTS TO BE LOCATED AT 20' O.C. MAX AND @ ALL CHANGES IN WALL WIDTHS.
- G.C. TO COORDINATE ALL UTILITIES IN EASEMENT


FS12 SITE WALL DETAIL
SCALE: 3/4" = 1'-0"



FS23 FOUNDATION PENETRATIONS, TYPICAL
SCALE: 3/4" = 1'-0"



FM01 SINGLE STORY FTG
SCALE: 3/4" = 1'-0"



FS STEM WALL FOOTING SCHEDULE
SCALE: N.T.S.

B&A Design Studio, Inc.

4017 W. 1st Street
Sanford, FL 32771
ph 407 829 8900
fax 407 829 2040
www.badesignstudios.com

FDS

ENGINEERING ASSOCIATE
288 Southall Lane, Suite 200, Maitland, FL 32751
P.O. Box 10000, Sanford, FL 32771
Certificate of Authorization No. 39161
CARLA A. BROWN, PE, FL #45628
SCOTT LEWIS, PE, FL #79790
DATE: November 9, 2023
PROJECT: PARK SQUARE HORIZONS WEST 4-UNIT - ADAMS END UNITS
FDS JOB NO.: _____





PARK SQUARE HORIZONS WEST 4-UNIT - ADAMS END UNITS




















title: _____

project no. 2022142
checked: AB
drawn: AB
date: 05-17-22
scale: _____

D1

NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED





B&A Design Studio, Inc.

4017 W. 1st Street
Sanford, FL 32771
ph: 407 820 8900
fax: 407 820 2040
www.badesignstudios.com

NCBDO

AI

AMERICAN INSTITUTE OF BUILDING DESIGN

FDS

288 Southall Lane, Suite 200, Maitland, FL 32751
www.fdseng.com

ENGINEERING ASSOCIATE

288 Southall Lane, Suite 200, Maitland, FL 32751
www.fdseng.com

PARK SQUARE

HORIZONS WEST

4-UNIT - ADAMS END UNITS

title:

project no. 2022142

checked:

drawn: AB

date: 05-17-22

scale:







D3

CD10 COLUMN DETAILS
SCALE: 3/4" = 1'-0"

WF100 BRG. WALL OVER FLOOR SYSTEM
SCALE: 3/4" = 1'-0"

WF06 TYP. CORNER FRAMING
SCALE: 3/4" = 1'-0"

WF06 TYP. CORNER FRAMING
SCALE: 3/4" = 1'-0"



B&A Design Studio, Inc.
4017 W. 1st Street
Seaford, FL 32771
ph 407 829 8900
fax 407 829 2040
www.badesignstudios.com









N.C.B.D.C.
AI
AMERICAN INSTITUTE OF BUILDING DESIGN

FDS
ENGINEERING ASSOCIATES
288 Southhall Lane, Suite 200, Maitland, FL 32751
www.fdseng.com
Certificate of Authorization No. 39161
□ CARL A. BROWN, PE - FL #5628
□ SCOTT LEWIS, PE - FL #79790
DATE: November 9, 2023
THE SEAL OF THE ENGINEER MUST BE PLACED ON THE DRAWING. THE STRUCTURAL DRAWING PROFESSIONAL MUST SIGN THE STRUCTURAL PORTION OF THE DRAWING.

PARK SQUARE
HORIZONS WEST
4-UNIT - ADAMS END UNITS

title:
project no. 2022142
checked:
drawn: AB
date: 05-17-22
scale:

D4



The structural design of this building is in accordance with the FLORIDA BUILDING CODE 7TH EDITION (2020) RESIDENTIAL and is certified as such.

B&A Design Studio, Inc.

4017 W. 1st Street
Sanford, FL 32711
ph: 407 829 8900
fax: 407 829 2040
www.badesignstudios.com

ALC
AMERICAN
INSTITUTION OF
BUILDING DESIGN

FDS
ENGINEERING ASSOCIATES
288 South Main Lane, Suite 200, Maitland, FL 32751
Phone: 407.829.8900
Fax: 407.829.2040
www.fdseng.com

FDS
ENGINEERING ASSOCIATES
288 South Main Lane, Suite 200, Maitland, FL 32751
Phone: 407.829.8900
Fax: 407.829.2040
www.fdseng.com

**PARK SQUARE
HORIZONS WEST
4-UNIT - ADAMS END UNITS**

title:
project no. 2022142
checked:
drawn: AB
date: 05-17-22
scale:
FP
STRUCTURAL

NOTE: DRAWINGS ON 11"x17" SHEET WILL BE ONE HALF THE SCALE NOTED